# THE WILDERNESS ACT OF SEPTEMBER 3, 1964

# Public Law 88-577 88th Congress, S. 4

#### AN ACT

To establish a National Wilderness Preservation System for the permanent good of the whole people, and for other purposes.

Be it enacted by the Senate and House of Representatives of the United States of America in Congress assembled.

### **SHORT TITLE**

Section 1. This Act may be cited as the "Wilderness Act".

### WILDERNESS SYSTEM ESTABLISHED— STATEMENT OF POLICY

Section 2.1ai. In order to assure that an increasing population, accompanied by expanding settlement and growing mechanization, does not occupy and modify all areas within the United States and its possessions, leaving no lands designated for preservation and protection in their natural condition, it is hereby declared to be the policy of the Congress to secure for the American people of present and tuture generations the benefits of an enduring resource of wilderness. For this prupose there is hereby established a National Wilderness Preservation System to be composed of rederalls owned areas designated by Congress as "wilderness areas", and these shall be administered for the use and enjoyment of the American people in such manner as will leave them unimpaired for future use and enjoyment as wilderness, and so as to provide for the protection of these areas, the preservation of their wilderness character, and for the gathering and dissemination of information regarding their use and enjoyment as wilderness; and no federal lands shall be designated as "wilderness areas" except as provided for in this Act or by a subsequent Act.

-b: The inclusion of an area in the National Wilderness Preservation System notwithstanding, the areashall continue to be managed by the Department and agency have jurisdiction thereover immediately before its inclusion in the National Wilderness Preservation System unless otherwise provided by Act of Congress. No appropriation shall be available for the payment of expenses or salaries for the administration of the National Wilderness Preservation System as a separate unit nor shall any appropriations be available for additional personnel stated as being required solely for the purpose of managing or administering areas solely because they are included within the National Wilderness Preservation System.

# **DEFINITION OF WILDERNESS**

Ic) A wilderness, in contrast with those areas where man and his own works dominate the landscape, is hereby recognized as an area where the earth and its community of life are untrammeled by man, where man himself is a visitor who does not remain. An area of wilderness is turther defined to mean in this Act an area of undeveloped Federal land retaining its primeval character and influence, without permanent improvements or human habitation, which is protected and

managed so as to preserve its natural conditions and which (1) generally appears to have been affected primarily by the forces of nature, with the imprint of man's work substantially unnoticeable; (2) has outstanding opportunities for softude or a primitive and unconfined type of recreation; (3) has all least five thousand acres of land or is of sufficient size as to make practicable its preservation and use in an unimpaired condition; and (4) may also contain ecological, geological, or other features of scientific, educational, scenic, or historical value.

### NATIONAL WILDERNESS PRESERVATION SYSTEM—EXTENT OF SYSTEM

Section 3.tal. All areas within the national forests classified at least 30 days before the effective date of this Act by the Secretary of Agriculture or the Chief of the Forest Service as "wilderness", "wild", or "canoe" are hereby designated as wilderness, areas. The Secretary of Agriculture shall—

(1) Within one year after the effective date of this Act, file a map and legal description of each wilderness area with the Interior and Insular Affairs Committees of the United States Senate and the House of Representatives, and such descriptions shall have the same force and effect as if included in this Act: Provided however, That correction of clerical and typographical errors in such legal descriptions and maps may be made.

(2) Maintain, available to the public, records pertaining to said wilderness areas, including maps and legal descriptions, copies of regulations governing them, copies of public notices of, and reports submitted to Congress regarding pending additions, eliminations, or modifications. Maps, legal descriptions, and regulations pertaining to wilderness areas within their respective jurisdictions also shall be available to the public in the offices of regional toresiers, natronal torest supervisors, and torest rangers.

Classification. (b) The Secretary of Agriculture shall, within ten years after the enactment of this Act, review, as to its suitability or nonsuliability for preservation as wilderness, each area in the national forests classified on the effective date of this Act by the Secretary of Agriculture or the Chief of the Forest Service as "primitive" and report his lindings to the President.

Presidential recommendation to Congress. The President shall advise the United States Senate and House of Representatives of his recommendations with respect to the designation as "wilderness" or other reclassification of each area on which review has been completed, together with maps and a definition of boundaries. Such advice shall be given with respect to not less than one-third of all the areas now classified as "primitive" within three years after the enactment of this Act, not less than two-thirds within seven years after the enactment of this Act, and the remaining areas within ten years after the enactment of this Act.

Congressional approval. Each recommendation of the President for designation as "wilderness" shall become effective only if so provided by an Act of Congress. Areas classified as

# 8560 - MANAGEMENT OF DESIGNATED WILDERNESS AREAS

"primitive" on the effective date of this Act shall continue to be administered under the rules and regulations affecting such areas on the effective date of this Act until Congress has determined otherwise. Any such area may be increased in size by the President at the time he submits his recommendations to the Congress by not more than five thousand acres with no more than one thousand two hundred and eighty acres of such increase in any one compact unit; if it is proposed to increase the size of any such area by more than five thousand acres or by more than one thousand two hundred and eighty acres in any one compact unit the increase in size shall not become effective until acted upon by Congress. Nothing herein contained shall limit the President in proposing, as part of his recommendations to Congress, the alteration of existing boundaries of primitive areas or recommending the addition of any contiguous area of national idrest lands predominantly of wilderness value. Notwithstanding any other provisions of this Act, the Secretary of Agriculture may complete his review and delete such areas as may be necessary, but not to exceed seven thousand acres, from the southern tip of the Gore Range-Eagles Nest Primitive Area, Colorado, if the Secretary determines that such action is in the public interest.

Report to President. (c) Within ten years after the effective date of this Act the Secretary of the Interior shall review every roadless area of five thousand contiguous acres or more in the national parks, monuments and other units of the national park system and every such area of, and every roadless island within, the national wildlife refuges and game ranges, under his jurisdiction on the effective date of this Act and shall report to the President his recommendation as to the suitability or nonsuitability of each such area or island for preservation as wilderness.

Presidential recommendation to Congress. The President shall advise the President of the Senate and the Speaker of the House of Representatives of his recommendation with respect to the designation as wilderness of each such area or island on which review has been completed, together with a map thereof and a definition of its boundaries. Such advice shall be given with respect to not less than one-third of the areas and islands to be reviewed under this subsection within three years after enactment of this Act, not less than two-thirds within seven years of enactment of this Act.

Congressional approval. A recommendation of the President for designation as wilderness shall become effective only if so provided by an Act of Congress. Nothing contained herein shall, by implication or otherwise, be construed to lessen the present statutory authority of the Secretary of the Interior with respect to the maintenance of roadless areas within units of the national park system.

Suitability. (d) 11 The Secretary of Agriculture and the Secretary of the Interior shall, prior to submitting any recommendations to the President with respect to the suitability of any area for preservation as wilderness—

Publication in Federal Register. (A) give such public notice of the proposed action as they deem appropriate, including publication in the Federal Register and in a newspaper having general circulation in the area or areas in the vicinity of the affected land;

Hearings. (B) hold a public hearing or hearings at a location or locations convenient to the area affected. The hearings shall be announced through such means as the respective Secretaries involved deem appropriate, including notices in the Federal Register and in newspapers of general circulation in the area: Provided, That if the lands involved are located in more than one State, at least one hearing shall be held in

each State in which a portion of the land lies:

(C) at least thirty days before the date of a hearing advise the Governor of each State and the governing board of each county, or in Alaska the borough, in which the lands are located, and Federal departments and agencies concerned, and invite such officials and Federal agencies to submit their views on the proposed action at the hearing or by no later than thirty days following the date of the hearing.

(2) Any views submitted to the appropriate Secretary under the provisions of (1) of this subsection with respect to any area shall be included with any recommendations to the President and to Congress with respect to such area.

Proposed modification. (e) Any modification or adjustment of boundaries of any wilderness area shall be recommended by the appropriate Secretary after public notice of such proposal and public hearing or hearings as provided in subsection (d) of this section. The proposed modification or adjustment shall then be recommended with map and description thereof to the President. The President shall advise the United States Senate and the House of Representatives of his recommendations with respect to such modification or adjustment and such recommendations shall become effective only in the same manner as provided for in subsections (b) and (c) of this section.

### **USE OF WILDERNESS AREAS**

Section 4. (a) The purposes of this Act are hereby declared to be within and supplemental to the purposes for which national forests and units of the national park and national wildlife refuge systems are established and administered and—

- (1) Nothing in this Act shall be deemed to be in interference with the purpose for which national forests are established as set forth in the Act of June 4, 1897 (30 Stat. 11), and the Multiple-Use Sustained-Yield Act of June 12, 1960 (74 Stat. 215).
- (2) Nothing in this Act shall modify the restrictions and provisions of the Shipstead-Nolan Act (Public Law 539, Seventy-first Congress, July 10, 1930; 46 Stat. 1020), the Thye-Blatnik Act (Public Law 733. Eightieth Congress, June 22, 1948; 62 Stat. 568), and the Humphrey-Thye-Blatnik-Andresen Act (Public Law 607. Eighty-fourth Congress, June 22, 1956; 70 Stat. 326), as applying to the Superior National Forest or the regulations of the Secretary of Agriculture.
- (3) Nothing in this Act shall modify the statutory authority under which units of the national park system are created further, the designation of any area of any park, monument, or other unit of the national park system as a wilderness area pursuant to this Act shall in no manner lower the standards evolved for the use and preservation of such park, monument, or other unit of the national park system in accordance with the Act of August 25, 1916, the statutory authority under which the area was created, or any other Act of Congress whichmight pertain to or affect such area, including, but not limited to, the Act of June 8, 1906 (34 Stat. 225; 16 U.S.C. 432 et seq.); section 3 (2) of the Federal Power Act (16 U.S.C. 796 (2)); and the Act of August 21, 1935 (49 Stat. 666; 16 U.S.C. 461 et seq.).
- (b) Except as otherwise provided in this Act, each agency administering any area designated as wilderness shall be responsible for preserving the wilderness character of the area and shall so administer such area for such other purposes for which it may have been established as also to preserve its wilderness character. Except as otherwise provided in this Act, wilderness areas shall be devoted to the public purposes of recreational, scenic, scientific, educational, conservation, and historical use.

### PROHIBITION OF CERTAIN USES

IC) Except as specifically provided for in this Act, and subject to existing private rights, there shall be no commercial enterprise and no permanent road within any wilderness area designated by this Act and, except as necessary to meet minimum requirements for the administration of the area for the purpose of this Act (including measures required in emergencies involving the health and safety of persons within the area), there shall be no temporary road, no use of motor vehicles, motorized equipment or motorboats, no landing of aircraft, no other form of mechanical transport, and no structure or installation within any such area.

#### SPECIAL PROVISIONS

- id. The following special provisions are hereby made:
- (1) Within wilderness areas designated by this Act the use of aircraft or motorboats, where these uses have already become established, may be permitted to continue subject to such restrictions as the Secretary of Agriculture deems desirable. In addition, such measures may be taken as may be necessary in the control of fire, insects, and diseases, subject to such conditions as the Secretary deems desirable.
- (2) Nothing in this Aci shall prevent within national forest wilderness areas any activity, including prospecting, for the purpose of gathering information about mineral or other resources, if such activity is carried on in a manner compatible with the preservation of the wilderness environment. Furthermore, in accordance with such program as the Secretary of the Interior shall develop and conduct in consultation with the Secretary of Agriculture, such areas shall be surveyed on a planned, recurring basis consistent with the concept of wilderness preservation by the Geological Survey and the Bureau of Mines to determine the mineral values, if any, that may be present; and the results of such surveys shall be made available to the public and submitted to the President and Congress.

Mineral leases, claims, etc. (3) Notwithstanding any other provisions of this Act, until midnight December 31, 1983, the nited States mining laws and all laws pertaining to mineral leasing shall, to the same extent as applicable prior to the effective date of this Act, extend to those national lorest lands designated by this Act as "wilderness areas"; subject, howto such reasonable regulations governing ingress and egress as may be prescribed by the Secretary of Agriculture consistent with the use of the land for mineral location and nevelopment and exploration, drilling, and production, and use of land for transmission lines, waterlines, telephone lines, or facilities necessary in exploring, drilling, producing, mining, and processing operations, including where essential the use of mechanized ground or air equipment and restoraas near as practicable of the surface of the land disturbed in performing prospecting, location, and, in oil and gas leasing, discovery work, exploration, drilling, and pro-duction, as soon as they have served their purpose. Mining locations lying within the boundaries of said wilderness areas shall be held and used solely for mining or processing opera-tions and uses reasonably incident thereto; and hereafter. subject to valid existing rights, all patents issued under the mining laws of the United States affecting national forest lands designated by this Act as wilderness areas shall convey title to the mineral deposits within the claim, together with the right to cut and use so much of the mature timber therefrom as may be needed in the extraction removal and beneficiation of the mineral deposits, if needed timber is not otherwise reasonably available, and if the timber is cut under sound principles of forest management as defined by the national

forest rules and regulations, but each such patent shall reserve to the United States all title in or to the surface of the lands and products thereof, and no use of the surface of the claim or the resources therefrom not reasonably required for carrying on mining or prospecting shall be allowed except as otherwise expressly provided in this Act: Provided, That, unless hereafter specifically authorized, no patent within wilderness areas designated by this Act shall issue after December 31, 1983, except for the valid claims existing on or before December 31, 1983. Mining claims located after the effective date of this Act within the boundaries of wilderness areas designated by this Act shall create no rights in excess of those rights which may be patented under the provisions of this subsection. Mineral leases, permits, and licenses cover lands within national forest wilderness areas designated by this Act shall contain such reasonable stipulations as may be prescribed by the Secretary of Agriculture for the protection of the wilderness character of the land consistent with the use of the land for the purposes for which they are leased, permitted, or licensed. Subject to valid rights then existing, effective January 1, 1984, the minerals in lands designated by this Act as wilderness areas are withdrawn from all forms of appropriation under the mining laws and from deposition under all laws pertaining to mineral leasing and all amendments thereto.

Water resources. (4) Within wilderness areas in the national forests designated by this Act, (1) the President may, within a specific area and in accordance with such regulations as he may deem desirable, authorize prospecting for water resources, the establishment and maintenance of reservoirs, water-conservation works, power projects, transmission lines, and other facilities needed in the public interest, including the road construction and maintenance essential to development and use thereof, upon his determination that such use or uses in the specific area will better serve the interests of the United States and the people thereof than will its denial; and (2) the grazing of livestock, where established prior to the effective date of this Act, shall be permitted to continue subject to such reasonable regulations as are deemed necessary by the Secretary of Agriculture.

- (5) Other provisions of this Act to the contrary notwith-standing, the management of the Boundary Waters Canoe Area, formerly designated as the Superior, bittle Indian Sioux, and Caribou Roadless Areas, in the Superior National Forest, Minnesota, shall be in accordance with regulations established by the Secretary of Agriculture in accordance with the general prupose of maintaining, without unnecessary restrictions on other uses, including that of timber, the primitive character of the area, particularly in the vicinity of lakes, streams, and portages: *Provided*, That nothing in this Act shall preclude the continuance within the area of any already established use of motorboats.
- (6) Commercial services may be performed within the wilderness areas designated by this Act to the extent necessary for activities which are proper for realizing the recreational or other wilderness purposes of the areas.
- (7) Nothing in this Act shall constitute an express or implied claim or denial on the part of the Federal Government as to exemption from State water laws.
- (8) Nothing in this Act shall be construed as affecting the jurisdiction or responsibilities of the several States with respect to wildlife and fish in the national forests.

# STATE AND PRIVATE LANDS WITHIN WILDERNESS AREAS

Section 5. (a) In any case where State-owned or privately owned land is completely surrounded by national forest lands within areas designated by this Act as wilderness, such State or private owner shall be given such rights as may be necessary to assure adequate access to such State-owned or privately owned land by such State or private owner and their successors in interest, or the State-owned land or privately owned land shall be exchanged for federally owned land in the same State of approximately equal value under authorities available to the Secretary of Agriculture:

Transfers, restriction. Provided. however, That the United States shall not transfer to a State or private owner any mineral interests unless the State or private owner relinguishes or causes to be relinquished to the United States the mineral interest in the surrounded land.

thi In any case where valid mining claims or other valid occupancies are wholly within a designated national forest widerness area, the Secretary of Agriculture shall, by reasonable regulations consistent with the preservation of the area as wilderness, permit ingress and egress to such surrounded areas by means which have been or are being customarily enjoyed with respect to other such areas similarly situated.

Acquisition. (c) Subject to the appropriation of funds by Congress, the Secretary of Agriculture is authorized to acquire privately owned land within the perimeter of any area designated by this Act as wilderness if (1) the owner concurs in such acquisition or (2) the acquisition is specifically authorized by Congress.

# GIFTS, BEQUESTS, AND CONTRIBUTIONS

Section 6. (a) The Secretary of Agriculture may accept gifts or bequests of land within wilderness areas designated by this Act for preservation as wilderness. The Secretary of Agriculture may also accept gifts or bequests of land adjacent to wilderness areas designated by this Act for preservation as wilderness if he has given sixty days advance notice thereof to the President of the Senate and the Speaker of the House of Representatives. Land accepted by the Secretary of Agriculture under this section shall become part of the wilderness area involved. Regulations with regard to any such land may be in accordance with such agreements, consistent with the policy of this Act, as are made at the time of such gift, or such conditions, consistent with such policy, as may be included in, and accepted with, such bequest.

(b) The Secretary of Agriculture or the Secretary of the Interior is authorized to accept private contributions and gifts to be used to further the purposes of this Act.

# ANNUAL REPORTS

Section 7. At the opening of each session of Congress, the Secretaries of Agriculture and Interior shall jointly report to the President for transmission to Congress on the status of the wilderness system, including a list and descriptions of the areas in the system, regulations in effect, and other pertinent information, together with any recommendations they may care to make.

# Congressional Grazing Guidelines

(Excerpt from House Report 96-1:26)

### Grazing in National Forest Wilderness Areas

Section 4(d)(4)(2) of the Wilderness Act states: "the grazing of livestock, where established prior to the effective date of this Act, shall be permitted to continue subject to such reasonable regulations as are deemed necessary by the Secretary of Agriculture."

The legislative history of this language is very clear in its intent that livestock grazing, and activities and the necessary facilities to support a livestock grazing program, will be per-mitted to continue in National Forest wilderness areas, when such grazing was established prior to classification of an area as wilderness.

including those areas established in the Wilderness Act of 1964. Congress has designated some 188 areas, covering lands administered by the Forest Service, Fish and Wildlife Service. National Park Service and Bureau of Land Management as components of the National Wilderness Preservation System. A number of these areas contain active grazing programs, which are conducted pursuant to existing authorities. In all such cases, when enacting legislation classifying an area as wilderness, it has been the intent of the Congress, based on solid evidence developed by testimony at public hearings, that the practical language of the Wilderness Act would apply to grazing within wilderness areas administered by all Federal agencies, not just the Forest Service. In fact, special language appears in all wilderness legislation, the intent of which is to assure that the applicable provisions of the Wilderness Act, including Section 4(d)(4)(2), will apply to all wilderness areas, regardless of agency jurisdiction.

Further, during the 95th Congress. Congressional committees became increasingly disturbed that, despite the language of section 4(d)(4)(2) of the Wilderness Act and despite a history of nearly 15 years in addressing and providing guidance to the wilderness management agencies for development of wilderness management policies. National Forest administrative regulations and policies were acting to dis-courage grazing in wilderness, or unduly restricting on-theground activities necessary for proper grazing management. To address this problem, two House Committee on Interior and Insular Affairs Reports (95-620 and 95-1321) specifically provided guidance as to how section 4(d)(4)(2) of the Wilderness. Act should be interpreted. This guidance appeared in tnese reports as follows

Section 4(d)(4)(2) of the Wilderness Act states that grazing in wilderness areas, if established prior to designa-tion of the area as wilderness, "shall be permitted to continue subject to such reasonable regulations as are deemed necessary by the Secretary of Agriculture." To clarity any lingering doubts, the committee wishes to stress that this language means that there shall be no curtailment of grazing permits or privileges in an area simply because it is designated as wilderness. As stated in the Forest Service regulations (36 CFR 293.7), grazing in wilderness areas ordinarily will be controlled under the general regulations governing grazing of livestock on National Forests....This includes the establishment of normal range allotments and allotment management plans. Furthermore, wilderness designation should not prevent the maintenance of existing tences or other livestock management improvements, nor the construction and maintenance of new fences or improvements which are consistent with allotment management plans and/or which are necessary for the protection of the range.

Despite the language of these two reports, RARE II hear-

ings and field inspection trips in the 96th Congress have revealed that National Forestadministrative policies on grazing in wilderness are subject to varying interpretations in the field, and are fraught with pronouncements that simply are not in accordance with Section 4(d)(4)(2) of the Wilder-Act. This had led to demands on the part of grazing permittees that section 4(d)(4)(2) of the Wilderness Act be amended to clarify the intentions of Congress. However because of the great diversity of conditions under which grazing uses (including different classes of livestock) are managed on the public lands, the Conferees feel that the original broad language of the Wilderness Act is best left unchanged. Any attempts to draft specific statutory language covering grazing in the entire wilderness system (presently administered by four separate agencies in two different Departments) might prove to be unduly rigid in a specific area, and deprive the land management agenof flexible opportunities to manage grazing in a creative and realistic site specific fashion.

Therefore, the conferees declined to amend section 4(d)(4)(2) of the Wilderness Act, agreeing instead to reaffirm the existing language and to include the following nationwide guidelines and specific statements of legislative policy. It is the intention of the conferees that the guidelines and policies be considered in the overall context of the pur-poses and direction of the Wilderness Act of 1964 and this Act, and that they be promptly, fully, and diligently implemented and made available to Forest Service personnel at all levels and to all holders of permits for grazing in Na-tional Forest Wilderness areas:

1. There shall be no curtailments of grazing in wilderness as simply because an area is, or has been designated as wilderness, not should wilderness designations be used as an excuse by administrators to slowly "phase out" grazing. Any adjustments in the numbers of livestock permitted to graze in wilderness areas should be made as a result of revisions in the normal grazing and land management planning and policy setting process, giving consideration to legal man-dates, range condition, and the protection of the range resource from deterioration.

It is anticipated that the numbers of livestock permitted to graze in wilderness would remain at the approximate levels existing at the time an area enters the wilderness system. management plans reveal conclusively that in-If land creased livestock numbers or animal unit months (AUMs) could be made available with no adverse impact on wilderness values such as plant communities, primitive recreation. and wildlife populations or habitat, some increases in AUMs may be permissible. This is not to imply, however, that wilderness lends itself to AUM or livestock increases and construction of substantial new facilities that might be appropriate for intensive grazing management in non-wilderness areas.

 The maintenance of supporting facilities, existing in an area prior to its classification as wilderness (including fences, line cabins, water wells and lines, stock tanks, etc.), is permissible in wilderness.

Where practical alternatives do not exist, maintenance or other activities may be accomplished through the occasional other activities may be accomplished through the occasional use of motorized equipment. This may include, for example, the use of backhoes to maintain stock ponds, pickup trucks for major fence repairs, or specialized equipment to repair stock watering facilities. Such occasional use of motorized equipment should be expressly authorized in the grazing permits for the area involved. The use of motorized equipment should be based on a rule of practical neces-

# 8560 - MANAGEMENT OF DESIGNATED WILDERNESS AREAS Congressional Grazing Guidelines (Excerpt from House Report 96-1126)

sity and reasonableness. For example, motorized equipment need not be allowed for the placement of small quantities of salt or other activities where such activities can reasonably and practically be accomplished on horseback or foot. On the other hand, it may be appropriate to permit the occasional use of motorized equipment to haul large quantities of salt to distribution points. Moreover, under the rule of reasonableness, occasional use of motorized equipment should be permitted where practical alternatives are not available and such use would not have a significant adverse impact on the natural environment. Such motorized equipment uses will normally only be permitted to nhose portions of a wilderness area where they had occurred prior to the area's designation as wilderness or are established by prior agreement.

- 3. The replacement or reconstruction of deteriorated facilities or improvements should not be required to be accomplished using "natural materials", unless the material and labor costs of using natural materials are such that their use would not impose unreasonable additional costs on grazing permittees.
- 4. The construction of new improvements or replacement of deteriorated facilities in wilderness is permissible if in accordance with those guidelines and management plans governing the area involved. However, the construction of new improvements should be primarily for the purpose of resource protection and the more effective management of these resources rather than to accommodate increased numbers of livestock.
- 5 The use of motorized equipment for emergency purposes such as rescuing sick animals or the placement of feed in emergency situations is also permissible. This privilege is to be exercised only in true emergencies, and should not be abused by permittees.

In summary, subject to the conditions and policies outlined above, the general rule of thumb on grazing management in wilderness should be that activities or facilities established prior to the date of an area's designation as wilderness should be allowed to remain in place and may be replaced when necessary for the permittee to properly administer the grazing program. Thus, if livestock grazing activities and facilities were established in an area at the time. Congress determined that the area was suitable for wilderness and placed the specific area in the wilderness system, they should be allowed to continue. With respect to areas designated as wilderness prior to the date of this Act, these guidelines shall not be considered as a direction to re-establish uses where such uses have been discontinued.

It is also the understanding of the conferees that the authorizing Committees intend to closely monitor the implementation of the guidelines through subsequent oversight hearings to insure that the spirit, as well as the letter, of the guidelines are adhered to by the Forest Service. Of course, the inclusion of these guidelines in this joint Statement of Managers does not preclude the Congress from dealing with the issue of grazing in wilderness areas statutorily in the future.


### Section 603 of

### THE FEDERAL LAND POLICY AND MANAGEMENT ACT OF 1976

(P.L. 94-579)

Sec. 603. (a) Within fifteen years after the date of approval of this Act, the Secretary shall review those roadless areas of five thousand acres or more and roadless islands of the public lands, identified during the inventory required by section 201(a) of this Act as having wilderness characteristics described in the Wilderness Act of September 3, 1964 (78 Stat. 890; 16 U.S.C. 1131 et seq.) and shall from time to time report to the President his recommendation as to the suitability or nonsuitability of each such area or island for preservation as wilderness: Provided, That prior to any recommendations for the designation of an area as wilderness the Secretary shall cause mineral surveys to be conducted by the Geological Survey and the Bureau of Mines to determine the mineral values, if any, that may be present in such areas: Provided further, That the Secretary shall report to the President by July 1, 1980, his recommendations on those areas which the Secretary has prior to November 1, 1975, formally identified as natural or primitive areas. The review required by this subsection shall be conducted in accordance with the procedures specified in section 3(d) of the Wilderness Act.

- (b) The President shall advise the President of the Senate and the Speaker of the House of Representatives of his recommendations with respect to designation as wilderness of each such area, together with a map thereof and a definition of its boundaries. Such advice by the President shall be given within two years of the receipt of each report from the Secretary. A recommendation of the President for designation as wilderness shall become effective only if so provided by an Act of Congress.
- (c) During the period of review of such areas and until Congress has determined otherwise, the Secretary shall continue to manage such lands according to his authority under this Act and other applicable law in a manner so as not to impair the suitability of such areas for preservation as wilderness, subject, however, to the continuation of existing mining and grazing uses and mineral leasing in the manner and degree in which the same was being conducted on the date of approval of this Act: Provided, That, in managing the public lands the Secretary shall by regulation or otherwise take any action required to prevent unnecessary or undue degradation of the lands and their resources or to afford environmental protection. Unless previously withdrawn from appropriation under the mining laws, such lands shall continue to be subject to such appropriation during the period of review unless withdrawn by the Secretary under the procedures of section 204 of this Act for reasons other than preservation of their wilderness character. Once an area has been designated for preservation as wilderness, the provisions of the Wilderness Act which apply to national forest wilderness areas shall apply with respect to the administration and use of such designated area, including mineral surveys required by section 4(d)(2)of the Wilderness Act, and mineral development, access, exchange of lands, and ingress and egress for mining claimants and occupants.



# 8560 - MANAGEMENT OF DESIGNATED WILDERNESS AREAS

### Table of Contents

- .01 Purpose
- .02 Objectives
- .03 Authority
- .04 Responsibility
- .05 Definitions
- .06 Policy
- .07 Mandate from Congress
- .08 Meaning of the Congressional Mandate

### .1 Goals of Wilderness Management

- .11 Preservation of Wilderness Character
  - A. Naturalness
  - B. Solitude
  - C. Special Features
- .12 Prohibition of Certain Uses
- .13 Minimum Tool
- A. Acceptable Tools
- .14 Visitor Use
  - A Acceptable Uses
  - B Acceptable Facilities
  - C Use Capacity
  - D Management Methods
  - E Visitors Risks
- .15 Nonconforming Uses
  - A. Valid Existing Rights
  - B Aircraft and Motorboats
  - C. Control of Fires. Insects, and Diseases
  - D. Gathering Information About Resources
  - E. Proposed Water Resource Facilities
  - F Existing Water Resource Facilities
  - G. Livestock Grazing
  - H. Minerals Management
  - Commercial Services
  - J. Access to Non-Federal Lands
- .16 Existing Structures and Installations
  - A. Conditions for Retention
  - B. Unobtrusive Materials
- .17 Acquisition of Non-Federal Lands
- .18 Research and Collection of Management Information
  - A. Research Conditions
  - B. Research as an Evaluation Tool
  - C. Research which Requires Wilderness Setting
  - D. Acceptable Equipment
- .19 Buffer Zones and Adjacent Lands

# .2 Administrative Functions

- .21 Wilderness Management Plans
  - A. Content

- B. Flexibility
- C. Zoning Between or Within a Wilderness Area
- .22 Coordination
  - A. Between State and District Offices
  - B. Lands Contiguous with Another Federal Agency's
  - C. Planning Efforts with Other Agencies
- .23 Wilderness Management Personnel
- .24 Visitor Information and Education
  - A. Minimal Regulation
  - B. Location of Information
  - C. Content

# .3 Specific Activities

- .31 Recreation and Visitor Use
  - A. Visitor Management
  - B. Improvements and Facilities
  - C. Fuelwood
  - D. Contests
- E. Recreational or Hobby Mineral Collecting
- .32 Cultural and Historic Resources
  - A. Use and Protection
  - B. Study and Management
  - C. Inventory and Evaluation
  - D. Recention of Historic Features
  - E. Management Action
  - F. Memorandum of Understanding
- 33 Forestry Resources
- A. Cutting Trees and Shrubs
- B. Cutting Trees for Administration Purposes
- C. Cutting Trees for Fuelwood
- D. Reforestation
- .34 Fish and Wildlife
  - A. Natural Balance
  - B. Hunting and Fishing
  - C. Fish and Wildlife Habitat
  - D. Wildlife Manipulation
  - E. Fish Stocking
  - F. Trapping
  - G. Rodents
  - H. Predators
- .35 Fire, Insect, and Disease Management
  - A. Fire Management
  - B. Control of Insects and Disease
- .36 Water Resources and Air Quality
  - A. Water Resource Management
- B. Air Quality
- .37 Rangeland Management

BLM MANUAL

- A. Livestock Grazing Operations
- B. Recreational Livestock
- C. Wild Horses and Burros
- .38 Minerals Management
  - A. Mining Law Administration
  - B. Mineral Leasing
  - C. Mineral Patents
  - D. Common Varieties of Mineral Materials
  - E. Paleontological Resources
- .39 Use of Motorized and Mechanical Equipment
  - A. Travel Within Wilderness
  - B. Administrative Use
  - C. Conditions of Use
- .4 Administrative Structures and Facilities
  - .41 Administrative Sites
  - .42 Fences
  - .43 Trails
  - .44 Airfields
  - .45 Heliports and Helispots
    - A. Heliports

- B. Helispots
- .46 Communication Facilities
- .47 Structures and Facilities Constructed. Used, and Proposed by Other Agencies
  - A. Periodic Review
  - B. Replacement
  - C. Signs, Instruments, and Other Minor Inprovements
- .5 Implementation of the Wilderness Management Policy
  - .51 Relationship to Wilderness Management Plan
    - A. Use of the Plan

# Glossary of Terms

# Appendices

- 1. The Wilderness Act of September 3, 1964.
- Congressional Grazing Guidelines.
- Section 603 of the Federal Land Policy and Management Act of 1976.

BLM MANUAL